

Dulles North Transit Center - Bid Item Summary

Item	Item Description	Unit	Quantity	Unit Price	Extension
1	MOBILIZATION	EA	1		
2	CONSTRUCTION SURVEY	LS	1		
3	SITE DEMOLITION	LS	1		
	SUBTOTAL				
	EARTHWORK				
4	FINE GRADING	CY	2058		
5	ROCK EXCAVATION	CY	150		
6	EXPORT	CY	7436		
	SUBTOTAL				
	STORM				
7	DI -1	EA	1		
8	DI -2B (L=4')	EA	1		
9	DI -2B (L=8')	EA	2		
10	DI -2C (L=8')	EA	1		
11	DI -3A	EA	1		
12	DI -3B (L=8')	EA	1		
13	DI -3B (L=10')	EA	1		
14	DI -3B (L=12')	EA	1		
15	ES-1 (15")	EA	1		
16	ES-1 (18")	EA	1		
17	DI TOP SLAB AND APPURTENANCES (L=12)	EA	2		
18	MH-1 WITH B-2 BASE AND FOOTING	EA	1		
19	15" (RCP CL III) PIPE	LF	261		
20	18" (RCP CL III) PIPE	LF	236		
21	21" (RCP CL III) PIPE	LF	34		
22	BIORETENTION BASIN	EA	1		
23	EC-1 CLASS I RIPRAP	TON	89		
	SUBTOTAL				
	LANDSCAPE				
24	TREES (8'-10') (2.5-3 IN. CALIPER)	EA	4		
25	PLANTING SHRUBS	EA	64		
26	POND SHALLOW WATER PLANTINGS	EA	6534		
	SUBTOTAL				
	PAVING, STRIPING AND SIGNAGE				
27	SM-9.5A (4")	TON	1705		
28	CTA (10")	TON	5082		
29	21-B (6")	TON	392		
30	CONCRETE PAVEMENT	SY	1177		
31	SIDEWALK	SY	1064		
32	MILL AND OVERLAY	SY	36395		
33	CRACK SEALING (LESS THAN 3/4" WIDTH)	LF	47000		
34	ASPHALT REPLACEMENT (CRACKS LARGER THAN 3/4" IN ACCORDANCE WITH PSSPGEN ITEM 38)	LF	700		
35	CURB AND GUTTER CG-2	LF	726		
36	CURB AND GUTTER CG-6	LF	1075		
37	CG-6R	LF	105		
38	CG-12 (TRUNCATED DOMES)	SF	434		
39	CONCRETE WHEEL STOPS	EA	24		
40	STRIPING 4" WIDTH (VDOT) (TYPE A) YELLOW	LF	4011		
41	STRIPING 4" WIDTH (VDOT) (TYPE A) WHITE	LF	22981		
42	STRIPING 6" WIDTH (TYPE A) WHITE	LF	1562		
43	STRIPING 12" WIDTH (TYPE A) WHITE	LF	205		
44	STRIPING 18" WIDTH (THERMOPLASTIC) WHITE	LF	261		
45	STRIPING 24" WIDTH (TYPE A) WHITE	LF	562		
46	PAVEMENT MARKINGS (ARROWS)	EA	5		
47	PAVEMENT MARKINGS ("STOP")	EA	42		
48	PAVEMENT MARKINGS (ACCESSIBLE PARKING)	EA	24		
49	BOLLARDS	EA	40		
50	SIGN - AREA	SF	313		
51	SIGN - POST	LF	964		
52	SIGN - FOOTING	EA	110		
53	MAINTENANCE OF TRAFFIC	LS	1		
54	MONUMENT SIGN	EA	1		
	SUBTOTAL				

Dulles North Transit Center - Bid Item Summary

Item	Item Description	Unit	Quantity	Unit Price	Extension
SITE FURNISHINGS					
55	4' VINYL COATED CHAIN LINK FENCE	LF	1453		
56	BIKE LOCKER (DOUBLE)	EA	6		
57	BUS SHELTER (8X50)	EA	3		
			SUBTOTAL		
SITE LIGHTS					
58	POLE MOUNTED LUMINAIRES	EA	51		
59	LIGHT POLE, 30' TALL	EA	2		
60	LIGHT POLE BASE	EA	2		
61	LIGHT POLE - CONDUIT & CONDUCTOR	LF	400		
62	ELECTRICAL POWER COMPONENTS	LS	1		
			SUBTOTAL		
EROSION CONTROL/LANDSCAPE					
63	CONSTRUCTION ENTRANCE W/ WASH RACK	EA	1		
64	SILT FENCE	LF	790		
65	SUPER SILT FENCE	LF	1119		
66	INLET PROTECTION	EA	20		
67	CHECK DAM	EA	2		
68	TREE PROTECTION	LF	784		
69	SEEDING/FERTILIZE	AC	0		
			SUBTOTAL		
ALLOWANCES (BIDDER CANNOT ADJUST QUANTITIES)					
A1	UNDERCUT	CY	1500		
A2	SUPPLEMENTAL MILLING AND OVERLAY	SY	1000		
A3	SUPPLEMENTAL MAINTENANCE OF TRAFFIC ITEMS				
	- VARIABLE MESSAGE BOARD	WEEK	4		
	-CERTIFIED FLAGGING PERSONNEL - TEAM OF CERTIFIED FLAGGERS WITH ALL EQUIPMENT	DAY	10		
	- TEMPORARY SIGNAGE - INCLUSIVE OF POST/FOOTING, INSTALLATION AND MAINTENANCE	SF	64		
A4	SUPPLEMENTAL LANDSCAPE ITEMS				
	- WATERING AND MAINTENANCE WARRANTY (BEYOND BASE CONTRACT REQMTS)	Month	6		
	- GENERAL GRADING AND SEEDING (TO TOPSOIL FILL DEPRESSIONS UP TO 18" IN DEPTH AND SEED)	SY	50		
A5	SPOT REPAIR FULL DEPTH PAVEMENT RECONSTRUCTION	SY	600		
A6	BREAK AND REPLACE CURB AND GUTTER	LF	250		
A7	ELECTRICAL DUTBANK 'DB1'	LF	350		
A8	ELECTRICAL DUTBANK 'DB2'	LF	350		
A9	SPOT ASPHALT REPLACEMENT	SY	500		
			ALLOWANCE SUBTOTAL		
				Subtotal	
					CONSTRUCTION TOTAL